

**Table B-2**  
**Data Summary Table: Asbestos Transmission Electron Microscopy Results**

TASK	FLOOR	LOCATION	DUST SAMPLE NOS.	FLOW RATE [LPM]	SAMPLE DURATION [MIN.]	SAMPLE AREA [SQ. CM]	RESULTS [STRUCTURES/SQ. CM]
<b>2 Building Materials Survey - Dust Sampling</b>							
	41	SE section of 41st floor by louvers [GH-12]	01	2	2	100	<891
	41	SE section of 41st floor by generator [GF-23]	02	2	2	100	3,332,285
	41	South side of 41st floor [ED-12]	03	2	2	100	2,140,000
	40	North side of 40th floor [CB-7]	04	2	2	100	214,000
	40	Center of 40th floor at HVAC cameras [CD-56]	05	2	2	100	273,920
	39	SE side of 39th floor, above ceiling tiles [GH-6]	06	2	2	100	4,280
	36	Center of 36th floor, carpet at stair A [CD-45]	07	2	2	100	67,766
	35	Mechanical Room, on top of Transformer [ED-34]	08	2	2	100	41,730
	34	Corridor at Center South, above ceiling tiles [ED-24]	09	2	2	100	891
	32	Open area in South Side, carpet [FE-12]	10	2	2	100	1,070
	31	Open area in South Side, above ceiling tiles [ED-2]	11	2	2	100	42,800
	30	Mail Room, distribution table [CD-56]	12	2	2	100	203,300
	28	Above ceillint, top of air duct [BC-7]	13	2	2	100	<891

**Table B-2**  
**Data Summary Table: Asbestos Transmission Electron Microscopy Results**

TASK	FLOOR	LOCATION	DUST SAMPLE NOS.	FLOW RATE [LPM]	SAMPLE DURATION [MIN.]	SAMPLE AREA [SQ. CM]	RESULTS [STRUCTURES/SQ. CM]
	27	Storage Room, inside Men's Room [CD-56]	14	2	2	100	11,591
	25	Above ceiling tiles [G-45]	15	2	2	100	<891
	24	Kitchen, inside cabinet [BC-34]	16	2	2	100	<891
	22	Corridor outside Info Service Office, above ceiling tiles [FD-34]	17	2	2	100	34,240
	21	Reception Counter, top of desk [ED-23]	18	2	2	100	205,440
	20	Above ceillint tiles, on top of air duct [GF-23]	19	2	2	100	64,200
	18	Top of radiator at window [H-12]	20	2	2	100	17,833
	17	Corridor at Main Elevators, above ceiling tiles [FE-45]	21	2	2	100	299,600
	15	Closet shelf at the end of Passenger Elevator Corridor [FE-23]	22	2	2	100	727,600
	14	Open area at South Side, above ceiling [FE-23]	23	2	2	100	25,680
	11	Shower Room, top of shelf [ED-34]	24	2	2	100	64,200
	10	Open area at East Side, above ceiling tiles [GH-34]	25	2	2	100	196,880
	9	Radiator at south window [FE-1]	26	2	2	100	94,160
	8	Staircase at Stair A, floor [FE-4]	27	2	2	100	178,333

**Table B-2**  
**Data Summary Table: Asbestos Transmission Electron Microscopy Results**

TASK	FLOOR	LOCATION	DUST SAMPLE NOS.	FLOW RATE [LPM]	SAMPLE DURATION [MIN.]	SAMPLE AREA [SQ. CM]	RESULTS [STRUCTURES/SQ. CM]
	7	South open area, above air duct [FE-12]	28	2	2	100	5,350
	5	West vent unit, on top of red metal drum [AB-45]	29	2	2	100	70,620
	5	West vent unit, on top of metal table (boxes) [BC-34]	30	2	2	100	770,400
	5	Floor under small air compressors [CD-23]	31	2	2	100	<891
	5	Top of green painted air receiver [FG-34]	32	2	2	100	278,200
	5	Under East vent unit [GF-78]	33	2	2	100	1,305,400
	4	Kitchen counter - metal [BC-45]	34	2	2	100	102,720
	3	Kitchen area [G-23]	35	2	2	100	269,640
	3	North side, under Gash [AB-67]	36	2	2	100	663,400
	2	Floor at the North Lobby [GH-78]	37	2	2	100	4,879,200
	M	Mezzanine Level, floor under Stairway [CD-23]	38	2	2	100	607,760
	1	1st Floor, at door [GF-56]	39	2	2	100	3,852,000
	1	1st Floor, at Staircase A entrance, carpet floor [FE-34]	40	2	2	100	269,640
		Field Blank	41				No Structures Detected

**Table B-2**  
**Data Summary Table: Asbestos Transmission Electron Microscopy Results**

TASK	FLOOR	LOCATION	DUST SAMPLE NOS.	FLOW RATE [LPM]	SAMPLE DURATION [MIN.]	SAMPLE AREA [SQ. CM]	RESULTS [STRUCTURES/SQ. CM]
		Field Blank	42				No Structures Detected
		Field Blank	43				No Structures Detected
		Field Blank	44				No Structures Detected
		Field Blank	45				No Structures Detected