

FINISH SCHEDULE

REVISIONS		
NO.	DATE	DESCRIPTION
A	7-20-74	GENERAL REVISION
B	11-17-74	REVISED AS REQUIRED
C	10-29-76	REVISED & CANCELLED WITH C

2ND FLOOR

ROOM OR SPACE	FLOOR	BASE	WALLS	CEILING	FINISH	REMARKS
ENTRY (ELEVATOR 1 & 2)	TERRAZZO	5" TERRAZZO	TRAVERTINE	SUSPENDED	MISCELLANEOUS	
ELEVATED SHOPPING WAY	TERRAZZO	5" TERRAZZO	TRAVERTINE	SUSPENDED	MISCELLANEOUS	
ELEVATOR # 24 VESTIBULE	CEMENT	4" RC	CB	SUSPENDED	REINFORCED CONCRETE	
ELEVATOR LOBBIES	TERRAZZO	5" TERRAZZO	TRAVERTINE	SUSPENDED	UNIMODUS C&H	
ALCOVES (ELEVATORS 1 & 2)	TERRAZZO	5" TERRAZZO	TRAVERTINE	SUSPENDED	UNIMODUS C&H	
PLAZA LEVEL LOBBY	TERRAZZO	5" TERRAZZO	TRAVERTINE	SUSPENDED	MISCELLANEOUS	
SECURITY CONTROL	CEMENT	—	CB	SUSPENDED	REINFORCED CONCRETE	
ELEVATOR ALCOVE (ELEV # 22)	CEMENT	—	CB	SUSPENDED	REINFORCED CONCRETE	
TELECOM CLOSET	VT	4" RC	GT - 8" HIGH	SUSPENDED	MD CS	
ELECTRIC CLOSET	CEMENT	—	CB	SUSPENDED	MD CS	
SERVICE CLOSET - MAIL STORAGE	CEMENT	—	CB	SUSPENDED	MD CS	
STAIRS	CEMENT	—	CB	SUSPENDED	MD CS	
ESCALATORS 1 & 2	CEMENT	—	CB	SUSPENDED	MD CS	
ELEVATOR VESTIBULE (ELEV # 24)	CEMENT	—	CB	SUSPENDED	MD CS	
EXIT PASSAGEWAY	CEMENT	—	CB	SUSPENDED	MD CS	
MEN'S & WOMEN'S TOILET	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	

3RD FLOOR

EMPLOYEES ACTIVITIES CENTER	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
OFFICE AREA	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
PANTRY	QUARRY TILE	5" QT	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
SERVING & LOUNGE AREA	4" RC	GB DW	GB DW	SUSPENDED	ACT-TYPE I	
DINING ROOMS 1 & 2	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
D.R. CORRIDOR	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CORRIDORS 1 & 2	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE HALL	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CHAIR & TABLE STORAGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
COAT CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
LINEN CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STORAGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
AUDIO STORAGE - MUSIC STORAGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
VESTIBULE & PASSAGE (ELEV # 24)	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
EP ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TOILET VESTIBULES	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
POWDER ROOMS - MEN'S WASHROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S TOILETS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S LOCKER ROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S SHOWER ROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
SERVICE CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELECOM CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELECTRIC CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ESCALATORS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

4TH FLOOR

DINING AREAS 1 & 2	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
LOUNGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE AREAS 1 & 2 & 3	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
KITCHEN & DINING	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STORE ROOM 1 & 2	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
OFFICE (KIT)	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
REUSE ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CORRIDORS 1 & 2	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STORAGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
OFFICE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TOILET VESTIBULES	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
VESTIBULE (ELEV # 24)	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S TOILETS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S WASHROOMS & POWDER ROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S LOCKER ROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
SERVICE CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELECTRIC CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELECOM CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ESCALATORS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

5TH FLOOR

MECHANICAL EQUIPMENT AREA	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ENGINEERS OFFICE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELECOM CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELECTRIC CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
MEN'S LOUNGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
MEN'S TOILET	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S SHOWER & LOCKER ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STORAGE ROOMS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

6TH TO 37TH FLOOR

OFFICE AREAS - EXCEPT	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
OFFICE & EQUIPMENT AREA	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
MEN'S & WOMEN'S TOILETS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
MEN'S WASHROOMS & WOMEN'S POWDER ROOMS	VT	4" RC	GT 8" HIGH	SUSPENDED	ACT-TYPE I	
VESTIBULES	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CONVEYOR ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELECOM CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELECTRIC CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELEPHONE CLOSETS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
VENDING MACHINE ALCOVE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
EP ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE HALL	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR LOBBY	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CORRIDORS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOMS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOM VESTIBULES	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

38TH FLOOR

MECHANICAL EQUIPMENT AREA	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOM (MG LEVEL)	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE HALL	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
CONVEYOR & PT. MACHINE ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
TELECOM CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SERVICE CLOSET	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
UPS ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
BATTERY ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
MOTOR GENERATOR ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
OFFICE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
SPACE PARTS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

39TH FLOOR

MECHANICAL EQUIPMENT AREA	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
GENERATOR ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
ELEVATOR MACHINE ROOMS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
FUEL TANK STORAGE	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
STAIRS	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	
RADIO ROOM	CEMENT	4" RC	GB DW	SUSPENDED	ACT-TYPE I	

NO.	DATE	DESCRIPTION
A	7-20-74	GENERAL REVISION
B	11-17-74	REVISED AS REQUIRED
C	10-29-76	REVISED & CANCELLED WITH C

BANKERS TRUST PLAZA

A FISHER BROTHERS PROJECT

GREENWICH AND LIBERTY ST. N. Y. N. Y.
SHREVE LAMB & HARMON ASSOCIATES PC
ARCHITECTS
475 PARK AVENUE SOUTH N. Y. N. Y. 10016
PETERSON AND BRICKBAUER
ASSOCIATED ARCHITECTS
919 THIRD AVENUE N. Y. N. Y. 10022
THE OFFICE OF JAMES RUDERMAN
STRUCTURAL ENGINEERS
315 MADISON AVENUE N. Y. N. Y. 10022
J A R O S . BAUM & BOLLE S
MECH. & ELEC. ENGINEERS
345 PARK AVENUE N. Y. N. Y. 10022

FINISH SCHEDULE SHEET NO. 2

PROJECT NUMBER	7101
DRAWING NUMBER	A 89
DATE	7-20-74
SCALE	AS SHOWN

FORMERLY A-73